

The Benefits of Working With Backwatch for Fleet Compliance — Checklist

backwatch.co.uk

Implementation Checklist

- ☐ System specification record: Which camera models, sensor types, and MDVR unit are installed; the position of each component; the cable routing; the input channel assignment on the MDVR; and the firmware versions of all active components at the time of installation.
- ☐ Commissioning test record: The results of the post-installation function test — each camera feed verified, sensor zone confirmed, indicator activation tested, MOIS detection tested, GPS embedding confirmed, portal connectivity confirmed. The commissioning record is signed by the installation engineer and dated.
- ☐ Compliance mapping: For DVS PSS installations, the record specifies which CMS, BSIS, and MOIS requirements each installed component satisfies. For FORS compliance, the record maps the installation against the FORS Silver or Gold specification. For LOLER compliance, the record identifies the lifting equipment zones covered by camera and sensor installation.